

Appendice G: Other Information

Impact Assessment Tables:

ISSUE	DESCRIPTION OF IMPACT	NATURE OF IMPACT	SPATIAL SCALE (EXTENT)	TEMPORAL SCALE (DURATION)	CERTAINTY SCALE (LIKELIHOOD)	SEVERITY / BENEFICIAL SCALE	SIGNIFICANCE PRE-MITIGATION	MITIGATION MEASURES	SIGNIFICANCE POST-MITIGATION
PLANNING & DESIGN PHASE									
GENERAL IMPACTS									
Compliance with relevant environmental legislation and policy	Failure to comply with existing policies and legal obligations can lead to the project conflicting with local, provincial and national policies, legislation etc. This can result in legal non-compliances, fines, delays in construction activity, overall project failure and undue disturbance to the natural environment.	DIRECT/ CUMULATIVE	Localized	Long-term	Possible	Severe	MODERATE NEGATIVE	<ul style="list-style-type: none"> All relevant legislation and policy must be consulted, and the proponent must ensure that the project is compliant with such legislation and policy. The relevant legislation and policies must include but not restricted to the following: NEMA, NWA, Local and District Spatial Development Frameworks, Eastern Cape Biodiversity Conservation Plan (ECBCP), and Local Municipal bylaws. 	LOW NEGATIVE
Stormwater runoff	Inappropriate stormwater design may lead to an increased risk of erosion on site.	DIRECT/ CUMULATIVE	Study area	Long-term	Probable	Severe	MODERATE NEGATIVE	<ul style="list-style-type: none"> Appropriate stormwater structures must be designed and implemented. Impermeable surfaces can be minimized through permeable surface technology, such as grassed gardens, verges and permeable paving etc. A Stormwater Management Plan (SMP) must be developed to advise and guide stormwater construction. 	LOW NEGATIVE
Waste management	Failure to plan for the storage and disposal of waste may lead to increased litter, pollution of the environment, unsanitary conditions, and health risks.	DIRECT INDIRECT	Localised	Medium-term	Probable	Moderately Severe	LOW NEGATIVE	<ul style="list-style-type: none"> A proper waste management plan for handling on site waste must be designed. An appropriate area where waste can be stored before disposal must be identified. Waste will be removed from site via municipal waste removal services. Consider recycling alternatives. 	LOW NEGATIVE
Visual aesthetics	Inappropriate architectural design may lead to visual and aesthetic impacts.	DIRECT	Study area	Permanent	Definite	Severe	HIGH NEGATIVE	<ul style="list-style-type: none"> The architectural design should be as unobtrusive and aesthetically pleasing as possible in terms of colour and building material used. Remove stockpiles before completing construction Proposed external lighting restrictions and guidelines. 	MODERATE NEGATIVE
Increased traffic	Inadequate planning for the increased traffic entering the site could result in traffic congestion during the construction phase.	DIRECT CUMULATIVE	Localised	Long-term	Probable	Moderately severe	MODERATE NEGATIVE	<ul style="list-style-type: none"> Appropriate planning must take place for the increased traffic to site: signage, speed limits, etc. Construction plant should avoid moving around during peak traffic hours 	LOW NEGATIVE

ISSUE	DESCRIPTION OF IMPACT	NATURE OF IMPACT	SPATIAL SCALE (EXTENT)	TEMPORAL SCALE (DURATION)	CERTAINTY SCALE (LIKELIHOOD)	SEVERITY / BENEFICIAL SCALE	SIGNIFICANCE PRE-MITIGATION	MITIGATION MEASURES	SIGNIFICANCE POST-MITIGATION
CONSTRUCTION PHASE									
GENERAL IMPACTS									
Compliance with relevant environmental legislation and policy	Failure of the contractor to implement mitigation measures specified in the EMPr and EA could result in fines, overall project failure or delays in construction and undue disturbance to the natural environment.	INDIRECT	Localised	Long-term	Possible	Moderately Severe	MODERATE NEGATIVE	<ul style="list-style-type: none"> The developer must employ an independent Environmental Control Officer (ECO) for the duration of the construction phase to ensure that construction is implemented according to conditions of the EA, EMPr and WUL. 	LOW NEGATIVE
Stormwater management	Inadequate stormwater infrastructure will lead to an increase in erosion risk.	DIRECT CUMULATIVE	Study area	Long-term	Probable	Severe	MODERATE NEGATIVE	<ul style="list-style-type: none"> Stormwater infrastructure must be implemented to capture stormwater and promote infiltration. The construction site must be managed (with silt traps and erosion berms etc.) to prevent pollution of environments surrounding the project site. The project area must be monitored by an ECO on a regular basis during construction. A Stormwater Management Plan (SMP) must be implemented to advise and guide stormwater construction. 	LOW NEGATIVE
General waste management	Littering on site may attract vermin and pollute the surrounding areas.	DIRECT	Study area	Permanent	Possible	Moderately severe	MODERATE NEGATIVE	<ul style="list-style-type: none"> There must be sufficient solid waste bins available for the temporary storage of waste. No waste must be buried or burned on site. Waste must be collected on a regular basis and disposed of at a licensed landfill site. Consider recycling options 	LOW NEGATIVE
Visual aesthetics of the area	The proposed project site will be transformed as a result of construction vehicles, large machinery and workers moving throughout the area.	DIRECT	Localised	Short-term	Probable	Slight	LOW NEGATIVE	<ul style="list-style-type: none"> All construction activity should take place during daylight working hours (i.e., 7am – 5pm). All construction activity and equipment must be limited to the demarcated areas. Storage of construction materials, stockpiles and waste must be positioned to avoid visibility from the adjacent roads. Building rubble and construction materials to be stored neatly. 	LOW NEGATIVE
	The development of the proposed residential development and associated infrastructure will visually transform the aesthetics of the site.	DIRECT CUMULATIVE	Localised	Permanent	Definite	Severe	HIGH NEGATIVE	<ul style="list-style-type: none"> Erosion, waste and dust to be mitigated as per the abovementioned mitigation measures. No visually intrusive practices (e.g., night lighting) will be allowed on site or in the surrounding areas. Good house-keeping to be implemented on site and waste to be collected on a regular basis. 	HIGH NEGATIVE
Dust control	Any levelling required for the construction at this site will increase the potential for dust. During the construction phase of the activity, materials will be moved to and from the project site and this could result in dust pollution not only from the materials, but also from the construction vehicles which will be operating on site. The effects of dust will be exacerbated during high wind conditions.	DIRECT	Study site	Short-term	Probable	Severe	MODERATE NEGATIVE	<ul style="list-style-type: none"> During windy periods un-surfaced and un-vegetated areas must be dampened down to reduce dust. Construction work to be halted during periods of strong winds. The maximum amount of vegetation cover must be maintained on site to prevent dust. Vehicles carrying dusty materials must be securely and properly covered before they leave the site. Excavations and other clearing activities must only take place during agreed working times and permitting weather conditions to avoid drifting of sand and dust into neighboring areas. Any complaints or claims emanating from dust issues must be attended to immediately by the Contractor. 	LOW NEGATIVE

ISSUE	DESCRIPTION OF IMPACT	NATURE OF IMPACT	SPATIAL SCALE (EXTENT)	TEMPORAL SCALE (DURATION)	CERTAINTY SCALE (LIKELIHOOD)	SEVERITY / BENEFICIAL SCALE	SIGNIFICANCE PRE-MITIGATION	MITIGATION MEASURES	SIGNIFICANCE POST-MITIGATION
Noise	It can be expected that there will be an increase in noise levels during the site preparation and construction phase of the development and may become a nuisance for surrounding residents. The increase in noise will be associated with the operation of construction vehicles, equipment and laborers.	DIRECT	Study area	Short-term	Probable	Moderately severe	LOW NEGATIVE	<ul style="list-style-type: none"> During construction, activities which include the movement of construction vehicles and the operation of machinery should be restricted to normal working hours (7am – 5pm weekdays, 7am – 1pm on Saturdays and no work on Sundays or public holidays). A complaints register must be kept on site and any complaints must be recorded and reported to the ECO. Construction equipment must be kept in good working order and, where appropriate, fitted with silencers which are kept in good working order. As construction workers operate in a noisy environment, it must be ensured that their working conditions comply with the requirements of the Occupational Health and Safety Act (Act No 85 of 1993). Where necessary, ear protection gear must be worn. 	LOW NEGATIVE
Construction traffic and Road Impacts	There will be an increase in traffic volumes including heavy construction vehicles along approach roads which may result in vehicle/ pedestrian collisions and degrade the road condition.	DIRECT	Study Area	Short-term	Probable	Moderately severe	LOW NEGATIVE	<ul style="list-style-type: none"> Residents must be made aware of the presence of construction vehicles through highly visible signage. Avoid transportation of construction materials during peak hours. Speed must be limited to 30km/hr on site. Overloading of vehicles must not occur. Whenever possible, construction vehicles should be limited to low-volume periods. Road condition should be recorded prior to construction vehicles making use of the roads and any damage caused by construction vehicles should be repaired immediately. Appropriate speed limits must be put in place. All construction vehicles should be parked onsite not to block traffic. 	LOW NEGATIVE
Disturbance to Faunal species	Large indigenous fauna such as large birds as well as small indigenous fauna such as snakes, lizards and frogs present on site may be impacted upon by construction activities.	DIRECT/ INDIRECT	Localised	Short-term	Definite	Moderately severe	LOW NEGATIVE	<ul style="list-style-type: none"> No fauna on site may be intentionally harmed or killed. All personnel should be made aware of the need to protect fauna on site. All open excavations must be barricaded or fenced. Excavations must be checked daily for trapped fauna and trapped animals be rescued and released. Injured fauna should be referred to an appropriate rehabilitation facility. 	LOW NEGATIVE
Soil Erosion	Exposed soils are easily susceptible to erosion by water runoff and wind during periods of heavy rainfall or strong winds. The non-cohesive nature of the <i>in-situ</i> material coupled with the lack of vegetation creates a potential for soil erosion at the proposed site. This may result in increased surface water flow as opposed to water absorption and subsequently contribute to soil erosion.	DIRECT	Study area	Short-term	Definite	Moderately severe	MODERATE NEGATIVE	<ul style="list-style-type: none"> Clearing of vegetation to only be undertaken immediately preceding construction. Temporary stabilization measures (e.g silt traps) should be implemented until the site is fully rehabilitated. Appropriate erosion control measures must be implemented to ensure that no erosion is taking place. At the first sign of erosion, the necessary remedial action must be taken. Care must be taken to ensure that runoff is well dispersed so as to limit erosion. A site-specific stormwater management plan should be implemented and managed to eliminate the potential of surface erosion. All temporarily impacted areas must be rehabilitated with indigenous vegetation as soon as construction in the particular area or phase of work is complete, i.e., 	LOW NEGATIVE

ISSUE	DESCRIPTION OF IMPACT	NATURE OF IMPACT	SPATIAL SCALE (EXTENT)	TEMPORAL SCALE (DURATION)	CERTAINTY SCALE (LIKELIHOOD)	SEVERITY / BENEFICIAL SCALE	SIGNIFICANCE PRE-MITIGATION	MITIGATION MEASURES	SIGNIFICANCE POST-MITIGATION
								rehabilitation is on-going throughout construction.	
General Waste Pollution	The construction phase of the activity will produce construction waste in the form of cleared vegetation, building rubble, excavated soil, excess concrete as well as general waste (e.g., litter from workers on site). The incorrect management of these wastes may result in pollution of the surrounding natural areas.	DIRECT	Localised	Short-term	Definite	Moderately severe	LOW NEGATIVE	<ul style="list-style-type: none"> Vegetation that is cleared from the site (and is not replanted or relocated as per the recommendations) must be removed to a registered garden refuse site. Staff must be trained to implement waste control and to identify hazardous waste. Construction material must be reused or recycled wherever possible. Other waste to be removed to a licensed landfill site. General good housekeeping must be implemented. No litter to remain on site. Disposal certificates must be obtained for all waste disposals. Spills must be avoided during transportation of waste material. Sufficient and appropriate weather-and scavenger-proof bins must be made available on site. 	LOW NEGATIVE
Impacts on Health, Safety and Fire Risk	The use of construction machinery during the construction phase poses a potential risk to the health and safety of people working at the construction site. The movement of construction vehicles also increases the risk of road accidents. The risk of accidents, fires and explosions must be mitigated effectively.	DIRECT	Localised	Short-term	Probable	Moderately Severe	LOW NEGATIVE	<ul style="list-style-type: none"> All relevant Health and Safety legislation as required in South Africa should be strictly adhered to, including but not limited to the Occupational Health and Safety Act, 1993 (No. 85 of 1993). Smoking should be prohibited in the vicinity of flammable substances. All traffic mitigation measures to be implemented as listed above Ensure availability of fire extinguishers All employees must be aware of emergency/contingency plans to ensure an understanding of the hazards and procedures required during and emergency situation. 	LOW NEGATIVE
Stockpiling	Incorrect storage of viable topsoil will result in the topsoil becoming sterile.	DIRECT	Localised	Short-term	Probable	Moderately severe	LOW NEGATIVE	<ul style="list-style-type: none"> Stockpile cannot be stored for a period longer than 12months. Stockpile heap cannot be higher than 2m as the weight of the soil may lead to seeds becoming sterile. Topsoil should only be moved once to prevent seeds from becoming sterile. No construction vehicles to ride over topsoil Subsoil and topsoil should always be kept separate. 	LOW NEGATIVE
Loss of vegetation	Clearing of natural vegetation will result in a range of issues including increasing the risk of erosion, reducing natural vegetation, loss of non-identified plant SCC, and increasing the risk of alien vegetation spreading.	DIRECT	Localised	Long-term	Definite	Moderately Severe	HIGH NEGATIVE	<ul style="list-style-type: none"> The construction footprint must be surveyed and demarcated prior to construction commencing. All contractors must be made aware of this demarcation. All areas outside the demarcated footprint will be considered as No-Go areas. No construction activities (temporary or permanent) will be allowed in these No-Go areas. Temporary infrastructure such as the site camp, laydown areas and storage areas must be placed in areas already transformed and within the construction footprint. No on-site fires will be permitted. 	MODERATE NEGATIVE
Loss of non-identified plant SCC		Direct	Localized	Short term	Unlikely	Severe	MODERATE NEGATIVE	<ul style="list-style-type: none"> Permits must be obtained to remove any plant SCC identified during the construction process. If none are identified, no permits will be required. Relocate or replant as many SCC as possible into the surrounding areas. 	LOW NEGATIVE

ISSUE	DESCRIPTION OF IMPACT	NATURE OF IMPACT	SPATIAL SCALE (EXTENT)	TEMPORAL SCALE (DURATION)	CERTAINTY SCALE (LIKELIHOOD)	SEVERITY / BENEFICIAL SCALE	SIGNIFICANCE PRE-MITIGATION	MITIGATION MEASURES	SIGNIFICANCE POST-MITIGATION
								<ul style="list-style-type: none"> No plant harvesting by construction staff will be allowed. 	
Spread of AIS		Direct and cumulative	Localized	Medium term	Probable	Severe	MODERATE NEGATIVE	<ul style="list-style-type: none"> Develop and implement an Alien Vegetation Management Plan to mitigate the establishment and spread of undesirable alien plant species during construction. All visible alien plants must be removed prior to top-and subsoil removal. Removal must occur through appropriate methods such as hand pulling, application of chemicals, cutting, etc. as in accordance with the NEMBA: Alien Invasive Species Regulations. 	LOW NEGATIVE

ISSUE	DESCRIPTION OF IMPACT	NATURE OF IMPACT	SPATIAL SCALE (EXTENT)	TEMPORAL SCALE (DURATION)	CERTAINTY SCALE (LIKELIHOOD)	SEVERITY / BENEFICIAL SCALE	SIGNIFICANCE PRE-MITIGATION	MITIGATION MEASURES	SIGNIFICANCE POST-MITIGATION
OPERATION PHASE									
GENERAL IMPACTS									
Stormwater runoff	Ensure that all stormwater infrastructure has been maintained and that it works properly.	DIRECT	Localised	Long-term	Probable	Moderately severe	MODERATE NEGATIVE	<ul style="list-style-type: none"> Stormwater management infrastructure must be properly maintained and monitored regularly. If the stormwater management measures put in place are deemed insufficient, a qualified engineer must be approached to assist with additional stormwater attenuation mechanisms and remediation. 	LOW NEGATIVE
Waste management	Inappropriate waste storage (general waste) and disposal practices may lead to litter, pollution, attraction of pests (flies, vermin) and general health risks.	DIRECT	Localised	Long-term	Probable	Moderately Severe	MODERATE NEGATIVE	<ul style="list-style-type: none"> All waste to be removed from site via municipal waste removal service regularly. In addition, an adequate backup system for waste management should be in place in case of service delivery strikes. Consider recycling options. 	LOW NEGATIVE
Utilization of Water Resources	The proposed development will rely entirely on water from the municipal supply to meet the daily consumption demands as estimated by the developer. This will place additional pressure on the current drought situation in the area.	DIRECT/ CUMULATIVE	Localised	Long-term	Definite	Severe	HIGH NEGATIVE	<ul style="list-style-type: none"> Excessive use of water to be avoided wherever possible. To ensure that all water reticulation infrastructure is maintained regularly to avoid leaks. Rainwater harvesting must be implemented to collect rainwater from the building drains and gutters. Make use of water saving products such as water saving toilets with a dual-flush valve, water saving taps with spray cartridges, water-saver shower heads and timed turn-off taps. Monitor water consumption to ensure water is utilized within the volumes made available by any relevant municipal drought regulations. 	MODERATE NEGATIVE
Electricity Usage	The proposed development will result in increased electricity usage due to increase in lighting and heating requirements. The overall electricity requirements will however be minimal.	DIRECT/ CUMULATIVE	Localised	Long-term	Definite	Severe	HIGH-NEGATIVE	<ul style="list-style-type: none"> Energy-saving strategies must be practiced such as using renewable energy (solar-energy) wherever possible. Utilize gas for cooking and heating. LED lighting must be implemented to reduce electricity consumption. 	MODERATE NEGATIVE
Invasives and Alien Species Management	There is a risk of alien invasive species spreading into surrounding areas. The lack of alien vegetation management may result in large scale alien plant invasion. However, should the property management implement an effective alien vegetation management plan both within the complex and, potentially within the surrounding areas, this could result in significantly positive improvement to alien species management.	DIRECT	Localised	Permanent	Probable	Moderate	MODERATE NEGATIVE	<ul style="list-style-type: none"> Areas disturbed with alien plants must be actively rehabilitated with indigenous vegetation or plants. Alien plant growth/regrowth within the complex and/or surrounding areas should also be monitored, and any such species should be removed on an ongoing basis. 	LOW NEGATIVE

ISSUE	DESCRIPTION OF IMPACT	NATURE OF IMPACT	SPATIAL SCALE (EXTENT)	TEMPORAL SCALE (DURATION)	CERTAINTY SCALE (LIKELIHOOD)	SEVERITY / BENEFICIAL SCALE	SIGNIFICANCE PRE-MITIGATION	MITIGATION MEASURES	SIGNIFICANCE POST-MITIGATION
NO-GO									
NO-GO <i>This refers to the current status quo and the risks and impacts associated with it</i>	None of the positive impacts and none of the negative impacts will occur if development does not proceed. Some job opportunities may be lost.	DIRECT	Localised	Long-term	Unlikely	Moderately severe	LOW NEGATIVE	<ul style="list-style-type: none"> No mitigation 	LOW NEGATIVE